

TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 1 of 27

The following sample(s) was/ were submitted and identified on behalf of the client as:

Sample Name : FIRE RATE DOWNLIGHT
Type No. : 1) FR1137W; 2) FR1175W; 3) FR1185W; 4) FR1193W;
5) FR1001W; 6) FR1003W; 7) FR1009W; 8) FR1011W
Test Item : Fire Resistance Test
Test Requested : BS 476-20:1987 Incorporating Amendment No.1.Fire tests on building materials and structures-Part 20:Method for determination of the fire resistance of elements of construction(general principles)
BS 476-21:1987 Fire tests on building materials and structures-Part 21: Methods for determination of the fire resistance of loadbearing elements of construction
Date of Receipt : Jan 28, 2015
Test Period : Jan 28, 2015 to Feb.12, 2015
Test Results : For further details, please refer to the following page(s)

***** To be continued*****

Signed for
SGS-CSTC Standards Technical
Services Co., Ltd. XM Branch Testing Center



Civi Huang
Authorized Signatory



This document is issued by the Company subject to its General Conditions of Service printed overleaf, available on request or accessible at <http://www.sgs.com/en/Terms-and-Conditions.aspx> and, for electronic format documents, subject to Terms and Conditions for Electronic Documents at <http://www.sgs.com/en/Terms-and-Conditions/Terms-e-Document.aspx>. Attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein. Any holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client and this document does not exonerate parties to a transaction from exercising all their rights and obligations under the transaction documents. This document cannot be reproduced except in full, without prior written approval of the Company. Any unauthorized alteration, forgery or falsification of the content or appearance of this document is unlawful and offenders may be prosecuted to the fullest extent of the law. Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 30 days only.

Attention: To check the authenticity of testing / inspection report & certificate, please contact us at telephone: (86-755) 8307 1443, or email: CN.Doccheck@sgs.com

SGS-CSTC Standards Technical Services Co., Ltd.
Xiamen Branch Testing Center Materials Laboratory

No.31 Xianghong Road, Xiang'an Torch Industrial Zone, Xiamen, Fujian Province, China. 361101 t (86-592) 5761588 f (86-592) 5765380 www.sgsgroup.com.cn
中国·福建·厦门·火炬(翔安)产业区翔虹路31号 邮编:361101 t (86-592) 5761588 f (86-592) 5765380 e sgs.china@sgs.com

TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 2 of 27

Test Summary

To determine the fire resistance of a timber floor assembly protected by a plasterboard ceiling designed to provide 90 minutes fire resistance, incorporating six downlight fittings, when tested in accordance with Clause 7 of BS 476-21:1987 "Fire tests on building materials and structures – Part 21: Methods for determination of the fire resistance of loadbearing elements of construction".

| Performance Criteria | Test Results |
|----------------------|--------------------|
| Integrity | 91min (No failure) |
| Insulation | 91min (No failure) |

Note: According to customer requirements, the test was discontinued after a period of 91 minutes.

Sample details and conditioning

The ceiling incorporated eight downlight fittings referenced as follows:

| Test Ref. | Model Ref. | Description |
|-----------|------------|----------------------------|
| A | FR1137W | Size: Φ90.0mm×71.3mm Round |
| B | FR1175W | Size: Φ97.0mm×69.0mm Round |
| C | FR1185W | Size: Φ90.0mm×71.3mm Round |
| D | FR1193W | Size: Φ97.0mm×69.0mm Round |
| E | FR1001W | Size: Φ84.0mm×46.5mm Round |
| F | FR1003W | Size: Φ92.0mm×46.5mm Round |
| G | FR1009W | Size: Φ84.0mm×46.5mm Round |
| H | FR1011W | Size: Φ92.0mm×46.5mm Round |

The floor assembly had overall nominal dimensions of 4696 mm long by 3200 mm wide. The unexposed surface of the floor comprised two layers of 15mm thick plasterboards, and both layers were screw fixed to the upside the floor joists.

The floor assembly was protected on its underside by a direct fixed ceiling, formed from two layers of 15mm thick plasterboard. both layers were screw fixed to the underside of the floor joists.

One layers of 50mm thick rockwool was filled into the cavity between the floor and the ceiling.

***** To be continued*****

TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 3 of 27

Test procedure

The ambient temperature at the beginning of the test was 16 °C.

The furnace temperature was measured by means of eight thermocouples distributed evenly in the furnace, with their measuring junctions 100 mm ± 10 mm from the exposed surface of the specimen. The furnace was controlled so that the mean of the eight thermocouple readings followed as closely as possible the time/temperature relationship specified in Clause 3.1 of BS 476-20:1987.

After the first five minutes of the test, the furnace pressure was maintained at 0±2 Pa at 1,000 mm from the notional floor level.

Thermocouples were provided to monitor the unexposed surface of the floor assembly and the output of all instrumentation was recorded at no less than one minute intervals. The locations and reference numbers of the various unexposed surface and internal thermocouples are shown in Figure 1.

Test data and information

Details of the specimen structure are shown in Figure 2 to 9. The photographs of the Down lights are shown in Photo 1 to 16.

Photographs of the test are shown in Photos 17 to 28. A summary of the observations made on the general behaviour of the specimen is given in Appendix 5.

The mean furnace temperature records are shown in Appendix 6, and the actual time-temperature curve of furnace in relation to the specified time-temperature curve is shown in Appendix 3.

The unexposed surface temperature records are shown in Appendix 7, and the individual temperatures recorded adjacent to the downlight fittings at mid-height of the cavity are shown in Appendix 8. The unexposed surface maximum and mean temperature curve are shown in Appendix 4.

The vertical deflection at the centre of the floor assembly was continuously measured during the test, and the data records is given in Appendix 9

Performance criteria

This test was according to performance criteria which specified in BS 476-21:1987, section 7.6 to determine the integrity and insulation of the specimen:

Integrity: A failure of the test construction to maintain integrity shall be deemed to have occurred when collapse or sustained flaming on the unexposed face occurs or the criteria given as follow for impermeability are exceeded.

***** To be continued*****

TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 4 of 27

- a) For situations where the cotton pad is suitable, failure shall be deemed to have occurred when flames and/or hot gases cause flaming or glowing of the cotton fibre pad.
- b) For situations where the use of the cotton pad is not suitable, failure shall be deemed to have occurred when either:
 - 1) the 6 mm diameter gap gauge can penetrate a through gap such that the end of the gauge projects into the furnace and the gauge can be moved in the gap for a distance of at least 150 mm; or
 - 2) the 25 mm diameter gap gauge can penetrate a through gap such that the end of the gauge projects into the furnace.

Insulation: Failure shall be deemed to have occurred when one of the following occurs:

- a) When the mean unexposed face temperature increases by more than 140°C above its initial value;
- b) When the temperature recorded at any positions on the unexposed face is in excess of 180°C above the initial mean unexposed face temperature;
- c) When integrity failure occurs

Remark:

- 1. The test results relate only to the specimen tested. Appendix A of BS 476-20 provides guidance information on the application of fire resistance tests and the interpretation of test data. Application of the result to assemblies of different dimensions or supported in other manners or incorporating different components should be the subject of a design appraisal.
- 2. The test was carried out by external laboratory assessed as competent.

***** To be continued*****

TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 5 of 27

Appendix 1: Schedule of components

Floor assembly (items 1 to 4)

1. Floor Joists

Material : Softwood timber joists
Overall section size : 45mm thickness×190mm deep
Density of Joist : 600kg/m³

2.Floorboards

Manufacturer : Knauf
Material : Gypsum plasterboard
Thickness : 2 layers, each 15mm thickness
Density : 727kg/m³
Fixing method : All board joints staggered with respect to adjacent layer and screw fixed to all joists using drywall steel screws, 35 mm long x 3.9 mm diameter screws for first layer and 55 mm long x 3.9 mm diameter screws for second layer, at 200 mm centres along joists and 150 mm centres along perimeter of floor.

3.Ceiling boards

Manufacturer : Knauf
Material : Gypsum plasterboard
Thickness : 2 layers, each 15mm thick
Density : 727kg/m³
Fixing method : All board joints staggered with respect to adjacent layer and screw fixed to all joists using drywall steel screws, 35 mm long x 3.9 mm diameter screws for first layer and 55 mm long x 3.9 mm diameter screws for second layer, at 200 mm centres along joists and 150 mm centres along perimeter of ceiling.

4.Rockwool

Manufacturer : Knauf
Thickness : 50mm
Density : 60kg/m³
Fixing method : filled into the cavity between the floor and the ceiling

***** To be continued*****



This document is issued by the Company subject to its General Conditions of Service printed overleaf, available on request or accessible at <http://www.sgs.com/en/Terms-and-Conditions.aspx> and, for electronic format documents, subject to Terms and Conditions for Electronic Documents at <http://www.sgs.com/en/Terms-and-Conditions/Terms-e-Document.aspx>. Attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein. Any holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client and this document does not exonerate parties to a transaction from exercising all their rights and obligations under the transaction documents. This document cannot be reproduced except in full, without prior written approval of the Company. Any unauthorized alteration, forgery or falsification of the content or appearance of this document is unlawful and offenders may be prosecuted to the fullest extent of the law. Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 30 days only.

Attention: To check the authenticity of testing / inspection report & certificate, please contact us at telephone: (86-755) 8307 1443, or email: CN.Doccheck@sgs.com

SGS-CTC Standards Technical Services Co., Ltd.
Xiamen Branch Testing Center Materials Laboratory

No.31 Xianghong Road, Xiang'an Torch Industrial Zone, Xiamen, Fujian Province, China. 361101 t (86-592) 5761588 f (86-592) 5765380 www.sgsgroup.com.cn
中国·福建·厦门·火炬(翔安)产业区翔虹路31号 邮编:361101 t (86-592) 5761588 f (86-592) 5765380 e sgs.china@sgs.com

TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 6 of 27

5.Specimen 'A'

Product Name : Fire rate Downlight

Manufacturer :

Type No. : FR1137W

Type : Round, fix down light

Overall dimensions and construction : See figure 2

Hole size in ceiling boards : 70mm

Materials :
i: cover: Die cast aluminium
ii: spring clip: Spring steel wire, nickel plated

Approx weight : 0.35kg

Details of fireproof material :
i: Manufacturer: Dongguan Fumei electronic materials Co., Ltd.
ii: Type: 90minutes fire resistance
iii:Thickness:1.5mm
iv: Location: Strip fitted external around flange of cover

6. Specimen 'B'

Product Name : Fire rate Downlight

Manufacturer :

Type No. : FR1175W

Type : Round, adjustable down light

Overall dimensions and construction : See figure 3

Hole size in ceiling boards : 83mm

Materials :
i: cover: Die cast aluminium
ii: spring clip: Spring steel wire, nickel plated

Approx weight : 0.36kg

Details of fireproof material :
i: Manufacturer: Dongguan Fumei electronic materials Co., Ltd.
ii: Type: 90minutes fire resistance
iii:Thickness:1.5mm
iv: Location: Strip fitted external around flange of cover

***** To be continued*****

TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 7 of 27

7. Specimen 'C'

Product Name : Fire rate Downlight
 Manufacturer :
 Type No. : FR1185W
 Type : Round, fix down light
 Overall dimensions and construction : See figure 4
 Hole size in ceiling boards : 70mm
 Materials :
 i: cover: Die cast aluminium
 ii: spring clip: Spring steel wire, nickel plated
 Approx weight : 0.35kg
 Details of fireproof material :
 i: Manufacturer: Dongguan Fumei electronic materials Co., Ltd.
 ii: Type: 90minutes fire resistance
 iii: Thickness: 1.5mm
 iv: Location: Strip fitted external around flange of cover

8. Specimen 'D'

Product Name : Fire rate Downlight
 Manufacturer :
 Type No. : FR1193W
 Type : Round, adjustable down light
 Overall dimensions and construction : See figure 5
 Hole size in ceiling boards : 83mm
 Materials :
 i: cover: Die cast aluminium
 ii: spring clip: Spring steel wire, nickel plated
 Approx weight : 0.36kg
 Details of fireproof material :
 i: Manufacturer: Dongguan Fumei electronic materials Co., Ltd.
 ii: Type: 90minutes fire resistance
 iii: Thickness: 1.5mm
 iv: Location: Strip fitted external around flange of cover

***** To be continued*****



SGS Standards Technical Services Co., Ltd.
 Xiamen Branch Testing Center Materials Laboratory

This document is issued by the Company subject to its General Conditions of Service printed overleaf, available on request or accessible at <http://www.sgs.com/en/Terms-and-Conditions.aspx> and, for electronic format documents, subject to Terms and Conditions for Electronic Documents at <http://www.sgs.com/en/Terms-and-Conditions/Terms-e-Document.aspx>. Attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein. Any holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client and this document does not exonerate parties to a transaction from exercising all their rights and obligations under the transaction documents. This document cannot be reproduced except in full, without prior written approval of the Company. Any unauthorized alteration, forgery or falsification of the content or appearance of this document is unlawful and offenders may be prosecuted to the fullest extent of the law. Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 30 days only.

Attention: To check the authenticity of testing / inspection report & certificate, please contact us at telephone: (86-755) 8307 1443, or email: CN.Doccheck@sgs.com

No.31 Xianghong Road, Xiang'an Torch Industrial Zone, Xiamen, Fujian Province, China. 361101 t (86-592) 5761588 f (86-592) 5765380 www.sgsgroup.com.cn
 中国·福建·厦门·火炬(翔安)产业区翔虹路31号 邮编:361101 t (86-592) 5761588 f (86-592) 5765380 e sgs.china@sgs.com

TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 8 of 27

9. Specimen 'E'

Product Name : Fire rate Downlight
 Manufacturer :
 Type No. : FR1001W
 Type : Round, fix down light
 Overall dimensions and construction : See figure 6
 Hole size in ceiling boards : 70mm
 Materials :
 i: cover: Die cast aluminium
 ii: shrapnel: Stainless steel
 Approx weight : 0.2kg
 Details of fireproof material :
 i: Manufacturer: Dongguan Fumei electronic materials Co., Ltd.
 ii: Type: 90minutes fire resistance
 iii: Thickness: 1.5mm
 iv: Location: Strip fitted external around flange of cover

10. Specimen 'F'

Product Name : Fire rate Downlight
 Manufacturer :
 Type No. : FR1003W
 Type : Round, adjustable down light
 Overall dimensions and construction : See figure 7
 Hole size in ceiling boards : 83mm
 Materials :
 i: cover: Die cast aluminium
 ii: spring clip: Spring steel wire, nickel plated
 Approx weight : 0.21kg
 Details of fireproof material :
 i: Manufacturer: Dongguan Fumei electronic materials Co., Ltd.
 ii: Type: 90minutes fire resistance
 iii: Thickness: 1.5mm
 iv: Location: Strip fitted external around flange of cover

***** To be continued*****



This document is issued by the Company subject to its General Conditions of Service printed overleaf, available on request or accessible at <http://www.sgs.com/en/Terms-and-Conditions.aspx> and, for electronic format documents, subject to Terms and Conditions for Electronic Documents at <http://www.sgs.com/en/Terms-and-Conditions/Terms-e-Document.aspx>. Attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein. Any holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client and this document does not exonerate parties to a transaction from exercising all their rights and obligations under the transaction documents. This document cannot be reproduced except in full, without prior written approval of the Company. Any unauthorized alteration, forgery or falsification of the content or appearance of this document is unlawful and offenders may be prosecuted to the fullest extent of the law. Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 30 days only.

Attention: To check the authenticity of testing / inspection report & certificate, please contact us at telephone: (86-755) 8307 1443, or email: CN.Doccheck@sgs.com

SGS-CTC Standards Technical Services Co., Ltd.
 Xiamen Branch Testing Center Materials Laboratory

No.31 Xianghong Road, Xiang'an Torch Industrial Zone, Xiamen, Fujian Province, China. 361101 t (86-592) 5761588 f (86-592) 5765380 www.sgsgroup.com.cn
 中国·福建·厦门·火炬(翔安)产业区翔虹路31号 邮编:361101 t (86-592) 5761588 f (86-592) 5765380 e sgs.china@sgs.com

TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 9 of 27

11. Specimen 'G'

Product Name : Fire rate Downlight
 Manufacturer
 Type No. : FR1009W
 Type : Round, fix down light
 Overall dimensions and construction : See figure 8
 Hole size in ceiling boards : 70mm
 Materials :
 i: cover: Die cast aluminium
 ii: shrapnel: Stainless steel
 Approx weight : 0.2kg
 Details of fireproof material :
 i: Manufacturer: Dongguan Fumei electronic materials Co., Ltd.
 ii: Type: 90 minutes fire resistance
 iii: Thickness: 1.5mm
 iv: Location: Strip fitted external around flange of cover

12. Specimen 'H'

Product Name : Fire rate Downlight
 Manufacturer
 Type No. : FR1011W
 Type : Round, adjustable down light
 Overall dimensions and construction : See figure 9
 Hole size in ceiling boards : 83mm
 Materials :
 i: cover: Die cast aluminium
 ii: spring clip: Spring steel wire, nickel plated
 Approx weight : 0.21kg
 Details of fireproof material :
 i: Manufacturer: Dongguan Fumei electronic materials Co., Ltd.
 ii: Type: 90 minutes fire resistance
 iii: Thickness: 1.5mm
 iv: Location: Strip fitted external around flange of cover

***** To be continued*****



This document is issued by the Company subject to its General Conditions of Service printed overleaf, available on request or accessible at <http://www.sgs.com/en/Terms-and-Conditions.aspx> and, for electronic format documents, subject to Terms and Conditions for Electronic Documents at <http://www.sgs.com/en/Terms-and-Conditions/Terms-e-Document.aspx>. Attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein. Any holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client and this document does not exonerate parties to a transaction from exercising all their rights and obligations under the transaction documents. This document cannot be reproduced except in full, without prior written approval of the Company. Any unauthorized alteration, forgery or falsification of the content or appearance of this document is unlawful and offenders may be prosecuted to the fullest extent of the law. Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 30 days only.

Attention: To check the authenticity of testing / inspection report & certificate, please contact us at telephone: (86-755) 8307 1443, or email: CN.Doccheck@sgs.com

SGS-CTC Standards Technical Services Co., Ltd.
 Xiamen Branch Testing Center Materials Laboratory

No.31 Xianghong Road, Xiang'an Torch Industrial Zone, Xiamen, Fujian Province, China. 361101 t (86-592) 5761588 f (86-592) 5765380 www.sgsgroup.com.cn
 中国·福建·厦门·火炬(翔安)产业区翔虹路31号 邮编: 361101 t (86-592) 5761588 f (86-592) 5765380 e sgs.china@sgs.com

TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 10 of 27

Load Calculations

1. Physical Parameters of Timber Joists

Measured Joist dimensions : 190 mm deep by 45 mm thick
 Mean spacing : 640 mm
 Effective span : 4500 mm
 Density of Joist : 600 kg/m³

2. Physical Parameters of Rockwool

Thickness : 50 mm
 Density : 60 kg/m³

3. Physical Parameters of Floorboards

Thickness : 2 layers, each 15 mm thick
 Density : 727 kg/m³

4. Physical Parameters of Ceiling boards

Thickness : 2 layers, each 15 mm thick
 Density : 727 kg/m³

5. Weight of Actual Timber Joists

Actual volume of Joist : 0.286 m³
 Actual weight of Joist : 171.6 kg

6. Weight of Actual Rockwool

Actual volume of Rockwool : 0.615 m³
 Actual weight of Rockwool : 36.9 kg

7. Weight of Actual Floorboards

Actual volume of Floorboards : 0.405 m³
 Actual weight of Floorboards : 294.4 kg

8. Weight of Actual Ceiling boards

Actual volume of Floorboards : 0.405 m³
 Actual weight of Floorboards : 294.4 kg

9. Actual Dead Weight

Actual Dead Weight of overall specimen : 797.3 kg

10. Actual Dead Load

Actual Dead Load per metre square : $(797.3 \times 9.81) / (4.5 \times 3.0)$
 579.4 N/m²
 59.1 kg/m²

Remark:

1. All values are nominal unless stated otherwise
2. All other details are as stated by the sponsor
3. All the specimens and floor assembly provided and install by sponsor

***** To be continued*****



SGS-CTC Standards Technical Services Co., Ltd.
 Xiamen Branch Testing Center Materials Laboratory

This document is issued by the Company subject to its General Conditions of Service printed overleaf, available on request or accessible at <http://www.sgs.com/en/Terms-and-Conditions.aspx> and, for electronic format documents, subject to Terms and Conditions for Electronic Documents at <http://www.sgs.com/en/Terms-and-Conditions/Terms-e-Document.aspx>. Attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein. Any holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client and this document does not exonerate parties to a transaction from exercising all their rights and obligations under the transaction documents. This document cannot be reproduced except in full, without prior written approval of the Company. Any unauthorized alteration, forgery or falsification of the content or appearance of this document is unlawful and offenders may be prosecuted to the fullest extent of the law. Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 30 days only.

Attention: To check the authenticity of testing / inspection report & certificate, please contact us at telephone: (86-755) 8307 1443, or email: CN.Doccheck@sgs.com

No.31 Xianghong Road, Xiang'an Torch Industrial Zone, Xiamen, Fujian Province, China. 361101 t (86-592) 5761588 f (86-592) 5765380 www.sgsgroup.com.cn
 中国·福建·厦门·火炬(翔安)产业区翔虹路31号 邮编:361101 t (86-592) 5761588 f (86-592) 5765380 e sgs.china@sgs.com

TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 11 of 27

Appendix 2: Details of test specimen




Figure 1 - Specimen General Plan

***** To be continued*****

TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 12 of 27




Figure 2 – Details of type No.: FR1137W




Figure 3 – Details of type No.: FR1175W




Figure 4 – Details of type No.: FR1185W




Figure 5 – Details of type No.: FR1193W

Note: the specimen details provided by the customer

***** To be continued*****

TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 13 of 27




Figure 6 – Details of type No.: FR1001W




Figure 7 – Details of type No.: FR1003W




Figure 8 – Details of type No.: FR1009W




Figure 9 – Details of type No.: FR1011W

Note: the specimen details provided by the customer

***** To be continued*****


TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 14 of 27

Appendix 3 - Furnace Temperature Curve



***** To be continued*****


TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 15 of 27

Appendix 4 - Unexposed Face Mean and Maximum Temperature Curve



TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 16 of 27

Appendix 5 –Test Observations

| Time (min) | Observation (All observations are from the exposed face unless noted otherwise) |
|---------------|--|
| 0 | Test started. |
| 12 | Coating of the plasterboard ceiling started to fall away. |
| 24 | Specimen 'A' fused. |
| 40 | The first layer of plasterboard ceiling started to sag slightly and joints began to open. |
| 48 | Specimen 'D' and 'E' fell away. |
| 50 | The first layer of plasterboard ceiling nearby specimen 'D' sagged seriously. |
| 52 | Specimen 'B', 'C' and 'H' fell away. |
| 54 | The first layer of plasterboard ceiling between specimen 'H' and 'F' fell away, and the specimen 'F' fell away at the same time. |
| 58 | Specimen 'G' fell away. |
| 61 | Specimen 'A' fell away. |
| 65 | Most of the first layer of plasterboard ceiling already fell away. |
| 68 | Some cracks appeared on second layer of plasterboard ceiling. |
| 75 | The second layer of plasterboard ceiling between specimen 'G' and 'H' fell away. |
| 78 | Lots of smoke release increased inside the furnace, resulting the observation from the exposed side discontinued. |
| 91 | Test terminated at sponsor's request. |

***** To be continued*****

TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 17 of 27

Appendix 6 – Furnace Temperature Records

| Time min | Specified Furnace Temperature °C | Actual Furnace Mean Temperature °C |
|-------------|-------------------------------------|---------------------------------------|
| 0 | 20 | 16 |
| 5 | 576 | 589 |
| 10 | 678 | 657 |
| 15 | 739 | 713 |
| 20 | 781 | 756 |
| 25 | 815 | 811 |
| 30 | 842 | 855 |
| 35 | 865 | 880 |
| 40 | 885 | 888 |
| 45 | 902 | 901 |
| 50 | 918 | 917 |
| 55 | 932 | 946 |
| 60 | 945 | 945 |
| 65 | 957 | 960 |
| 70 | 968 | 972 |
| 75 | 979 | 980 |
| 80 | 988 | 984 |
| 85 | 997 | 1000 |
| 90 | 1006 | 995 |
| 91 | 1008 | 993 |

***** To be continued*****

TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 18 of 27

Appendix 7 –Unexposed Surface Temperature Records

| Time min | TC No.201 °C | TC No.202 °C | TC No.203 °C | TC No.204 °C | TC No.205 °C | TC No.206 °C | TC No.207 °C | TC No.208 °C | TC No.209 °C | Mean Temp °C | Mean Temp Rise °C | Max Temp Rise °C |
|-------------|--------------------|--------------------|--------------------|--------------------|--------------------|--------------------|--------------------|--------------------|--------------------|--------------------|----------------------------|---------------------------|
| 0 | 14.1 | 13.9 | 13.9 | 13.9 | 13.8 | 14.0 | 13.9 | 13.8 | 13.7 | 13.9 | 0.0 | 0.2 |
| 5 | 14.5 | 14.3 | 14.3 | 14.4 | 14.2 | 14.5 | 14.3 | 14.3 | 14.2 | 14.3 | 0.4 | 0.6 |
| 10 | 14.8 | 14.6 | 14.5 | 14.7 | 14.4 | 14.6 | 14.6 | 14.5 | 14.4 | 14.6 | 0.7 | 0.9 |
| 15 | 15.1 | 15.5 | 15.0 | 15.1 | 15.1 | 15.4 | 15.1 | 14.9 | 15.0 | 15.2 | 1.2 | 1.6 |
| 20 | 16.2 | 20.0 | 16.1 | 16.5 | 19.7 | 17.8 | 18.1 | 15.6 | 16.7 | 17.7 | 3.8 | 6.1 |
| 25 | 18.8 | 29.2 | 18.7 | 19.6 | 30.9 | 23.3 | 25.5 | 17.6 | 20.7 | 23.4 | 9.5 | 17.0 |
| 30 | 23.2 | 39.6 | 23.5 | 24.1 | 42.9 | 28.0 | 34.9 | 20.6 | 26.5 | 30.7 | 16.7 | 29.0 |
| 35 | 29.2 | 49.2 | 30.3 | 29.4 | 53.3 | 33.7 | 46.0 | 25.0 | 34.4 | 38.3 | 24.4 | 39.4 |
| 40 | 36.6 | 57.1 | 39.1 | 36.0 | 60.3 | 40.1 | 56.2 | 32.9 | 42.4 | 45.8 | 31.9 | 46.4 |
| 45 | 45.8 | 62.8 | 49.7 | 43.2 | 65.6 | 46.7 | 63.5 | 39.1 | 50.6 | 53.4 | 39.5 | 51.7 |
| 50 | 56.0 | 66.6 | 55.1 | 50.2 | 66.0 | 52.9 | 67.9 | 48.3 | 56.6 | 58.8 | 44.9 | 54.0 |
| 55 | 64.4 | 69.5 | 60.2 | 56.6 | 66.2 | 59.1 | 69.1 | 55.8 | 59.4 | 63.4 | 49.5 | 55.6 |
| 60 | 69.6 | 69.9 | 63.6 | 62.0 | 66.6 | 63.8 | 69.2 | 61.0 | 61.4 | 66.3 | 52.4 | 56.0 |
| 65 | 72.2 | 70.2 | 65.1 | 65.2 | 66.9 | 67.7 | 69.3 | 64.8 | 64.1 | 67.9 | 54.0 | 58.3 |
| 70 | 72.9 | 70.4 | 65.5 | 66.5 | 67.0 | 70.4 | 69.5 | 66.9 | 65.7 | 68.5 | 54.5 | 59.0 |
| 75 | 73.0 | 70.6 | 65.9 | 68.3 | 67.3 | 72.5 | 69.7 | 67.6 | 66.0 | 69.0 | 55.1 | 59.1 |
| 80 | 73.1 | 70.7 | 66.7 | 69.1 | 67.7 | 74.0 | 69.9 | 68.8 | 66.3 | 69.5 | 55.5 | 60.1 |
| 85 | 73.3 | 70.9 | 67.6 | 70.6 | 68.0 | 75.9 | 70.0 | 69.2 | 67.3 | 70.1 | 56.2 | 62.0 |
| 90 | 74.7 | 71.3 | 69.5 | 73.8 | 71.7 | 80.5 | 71.5 | 71.0 | 70.1 | 72.2 | 58.3 | 66.6 |
| 91 | 75.0 | 71.4 | 69.9 | 74.9 | 73.0 | 81.0 | 72.2 | 72.3 | 71.9 | 72.8 | 58.9 | 67.1 |

***** To be continued*****

TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 19 of 27

Appendix 8 – Individual Temperatures Recorded Adjacent to the Downlight Fittings at
Mid-height of the Cavity

| Time min | TC No.210 ℃ | TC No.211 ℃ | TC No.212 ℃ | TC No.213 ℃ | TC No.214 ℃ | TC No.215 ℃ |
|-------------|-------------------|-------------------|-------------------|-------------------|-------------------|-------------------|
| 0 | 14.3 | 14.2 | 14.0 | 14.8 | 14.6 | 14.5 |
| 5 | 14.7 | 16.8 | 14.8 | 18.0 | 16.0 | 19.2 |
| 10 | 24.9 | 19.9 | 40.8 | 38.8 | 30.2 | 26.8 |
| 15 | 63.7 | 40.3 | 65.9 | 58.8 | 69.8 | 62.0 |
| 20 | 84.2 | 63.1 | 74.9 | 69.4 | 85.4 | 80.3 |
| 25 | 88.1 | 74.0 | 80.8 | 75.8 | 88.6 | 84.7 |
| 30 | 89.8 | 77.9 | 83.2 | 83.3 | 92.8 | 90.1 |
| 35 | 93.2 | 84.5 | 86.3 | 93.5 | 95.5 | 100.1 |
| 40 | 96.7 | 90.3 | 106.4 | 99.5 | 98.4 | 103.4 |
| 45 | 98.3 | 94.7 | 114.6 | 100.3 | 101.5 | 104.5 |
| 50 | 99.0 | 94.9 | 116.0 | 101.8 | 103.0 | 105.9 |
| 55 | 99.4 | 95.4 | 117.2 | 102.4 | 104.0 | 107.5 |
| 60 | 99.9 | 97.9 | 118.5 | 102.9 | 104.9 | 110.4 |
| 65 | 100.1 | 102.4 | 119.4 | 103.4 | 109.7 | 111.3 |
| 70 | 101.7 | 110.1 | 120.9 | 104.0 | 123.4 | 114.2 |
| 75 | 116.9 | 135.3 | 155.2 | 111.1 | 159.0 | 146.1 |
| 80 | 161.3 | 163.3 | 205.6 | 136.0 | 190.0 | 175.1 |
| 85 | 286.5 | 180.1 | 219.4 | 151.0 | 309.1 | 258.9 |
| 90 | 324.7 | 242.0 | 265.2 | 211.7 | 345.1 | 295.8 |
| 91 | 339.5 | 258.3 | 295.5 | 245.9 | 350.7 | 311.2 |

***** To be continued*****

TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 20 of 27

Appendix 9 - Deflection of the floor assembly during the test

| Time min | Central Vertical Deflection mm |
|-------------|-----------------------------------|
| 0 | 0.0 |
| 5 | 5.0 |
| 10 | 6.3 |
| 15 | 6.0 |
| 20 | 4.9 |
| 25 | 4.5 |
| 30 | 4.7 |
| 35 | 4.6 |
| 40 | 4.7 |
| 45 | 4.6 |
| 50 | 4.9 |
| 55 | 5.5 |
| 60 | 6.1 |
| 65 | 6.2 |
| 70 | 5.9 |
| 75 | 5.8 |
| 80 | 6.4 |
| 85 | 8.3 |
| 90 | 11.7 |
| 91 | 12.3 |

Note: A negative value indicates deflection away from the furnace

***** To be continued*****

TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 21 of 27

Photo Appendix:




Photo 1: Front view of FR1137W



Photo 2: Side view of FR1137W




Photo 3: Front view of FR1175W



Photo 4: Side view of FR1175W

***** To be continued*****

TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 22 of 27



Photo 5: Front view of FR1185W



Photo 6: Side view of FR1185W



Photo 7: Front view of FR1193W



Photo 8: Side view of FR1193W

***** To be continued*****

TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 23 of 27




Photo 9: Front view of FR1001W



Photo 10: Side view of FR1001W




Photo 11: Front view of FR1003W



Photo 12: Side view of FR1003W

***** To be continued*****

TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 24 of 27




Photo 13: Front view of FR1009W



Photo 14: Side view of FR1009W



Photo 15: Front view of FR1011W



Photo 16: Side view of FR1011W

***** To be continued*****

TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 25 of 27



Photo 17: The exposed surface of the specimen before the test



Photo 18: The unexposed surface of the specimen before the test




Photo 19: The unexposed surface of the specimen after a test duration of 15 minutes.



Photo 20: The exposed surface of the specimen after a test duration of 24 minutes, showing the specimen 'A' fused.

***** To be continued*****

TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 26 of 27



Photo 21: The unexposed surface of the specimen after a test duration of 30 minutes.




Photo 22: The unexposed surface of the specimen after a test duration of 45 minutes.



Photo 23: The exposed surface of the specimen after a test duration of 48 minutes, showing the specimen 'D' and 'E' fell away and the nearby first layer of plasterboard ceiling started to sag slightly and joints began to open.



Photo 24: The exposed surface of the specimen after a test duration of 54 minutes, showing the specimen 'B' and 'C' fell away and a part of first layer of plasterboard ceiling fell away.

***** To be continued*****

TEST REPORT

No. : XMCCM150100122

Date : Mar.11, 2015

Page: 27 of 27




Photo 25: The unexposed surface of the specimen after a test duration of 60 minutes.



Photo 26: The exposed surface of the specimen after a test duration of 68 minutes, showing cracks appeared on second layer of plasterboard ceiling.



Photo 27: The unexposed surface of the specimen after a test duration of 90 minutes.



Photo 28: The unexposed surface of the specimen after the test

SGS authenticate the photo on original report only

***** End of report*****